

Bid Opening  
Date: May 6, 2021  
Time: 2:25 P.M.

**ADDENDUM NO. #1**  
**FOR**  
**2021 LRIP Curb & Gutter-Main Street**

**1. Error in bid item #16. The quantity showed 12,000. The quantity should be 1,200. Please use the revised bid form.**



# Engineering Department

400 La Crosse St., La Crosse, WI 54601 • (608) 789-7505 • Fax: (608) 789-8184  
<http://www.cityoflacrosse.org>

## CITY OF LACROSSE ENGINEERING BID TAB

**Contract**  
**Date**

2021 LRIP Curb & Gutter - Main Street  
 May 6th, 2021 @ 2:25 p.m.

Section Title	Line Item	Item Code	Item Description	UofM	Quantity	Unit Price	Total
Removals	Required						
	1	10	Remove Concrete Curb & Gutter	LF	3764		
	2	11	Remove Concrete Flatwork (Any Thickness)	SF	7000		
	3	15.01	Remove Bituminous Concrete Pavement (Standard)	SY	10,200		
	4	5.01	Sawing (Concrete)	LF	148		
	5	5.02	Sawing (Bituminous)	LF	382		
	6	1001	Removal of Concrete Median	LS	1		
<b>SUBTOTAL- Section 1</b>							
Installations	Required						
	7	125.01	Curb & Gutter (Standard)	LF	3489		
	8	125.08	High-Early Curb & Gutter (Standard)	LF	275		
	9	100.02	Base Course (Furnished, Compacted, & Graded) (7")	SY	9500		
	10	130.03	Bituminous Concrete Pavement (Res/bus route)	SY	9500		
	11	120.03	Concrete Flatwork (6")	SF	1161		
	12	120.07	High-Early Concrete Flatwork (6")	SF	1000		
	13	120.02	Concrete Flatwork (5")	SF	2400		
	14	120.01	Concrete Flatwork (4")	SF	3000		
	15	121.01	Truncated Dome Warning Fields (2'x4')	EA	32		
	16	140.01	Restoration (Hydro)	SY	1,200		
	17	145.01	Temporary Traffic Control	LS	1		
	18	135.01	Erosion Control Installation & Maintenance	LS	1		
	19	114.01	Drilled Tie Bars	EA	8		
	20	1002	Installation of Concrete Median (Nose, Inc. V-Lock)	LS	1		
<b>SUBTOTAL- Section 2</b>							
Storm Sewer	Required						
	21	225.02	Replace Catch Basin (Type B)	EA	3		



# Engineering Department

400 La Crosse St., La Crosse, WI 54601 • (608) 789-7505 • Fax: (608) 789-8184  
<http://www.cityoflacrosse.org>

## CITY OF LACROSSE ENGINEERING BID TAB

**Contract**  
**Date**

2021 LRIP Curb & Gutter - Main Street  
 May 6th, 2021 @ 2:25 p.m.

Section Title	Line Item	Item Code	Item Description	UofM	Quantity	Unit Price	Total
	22	207.15	Replace PVC SDR-35 Storm Sewer (12")	LF	100		
	23	230.01	Connect to Existing Storm Manhole (PVC up to 12")	EA	1		
	24	234.01	Replace Pre-Cast Concrete Top	EA	6		
	25	150.01	Core & Pour Manhole Finishing	EA	7		
	26	232.01	Replace Rings (Manhole)	IN	20		
	27	231.01	Adjust Existing Manhole Structures to final Elev.	EA	5		
	28	232.03	Replace Rings (Catch Basin Type B)	IN	36		
	29	231.02	Adjust Existing Catch Basin to final Elev.	EA	6		
<b>SUBTOTAL- Section 3</b>							
Water	Required						
	30	408.01	Replace DIP Class 350 Water Main (6")	LF	40		
	31	411.01	New Resilient-Seated Gate Valve (6")	EA	4		
	32	416.01	New Hydrant and Valve Cluster Group (Short Side)	EA	1		
<b>SUBTOTAL- Section 4</b>							
Sanitary Sewer	Required						
	33	622.02	Replace Standard Pre-Cast Concrete Manhole (10-14FT Deep)	EA	2		
<b>SUBTOTAL- Section 5</b>							
Traffic	Required						
	34	971.01	Pavement Markings (EP)	LS	1		
<b>SUBTOTAL- Section 6</b>							
<b>TOTAL-Sections 1-6</b>							